



# Erosion and Sediment Control Requirements

---

1. Sediment and erosion control devices shall be installed and functioning prior to beginning any project earth disturbing activities.
2. All sediment and erosion controls shall be inspected until construction is complete, the site is permanently stabilized.
3. All erosion control devices shall be properly maintained during all phases of construction until the completion of all construction activities and all disturbed areas have been permanently stabilized. Additional control devices may be required during construction in order to control erosion and/or offsite sedimentation. All temporary control devices shall be removed once construction is complete and the site is permanently stabilized.
4. All sediment and erosion control devices shall be inspected once every seven (7) calendar days. Damaged, ineffective, or incorrectly installed devices shall be repaired or replaced, as necessary, within 48 hours of identification.
5. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than fourteen (14) days after work has ceased.

**COMMUNITY  
DEVELOPMENT  
SERVICES**

**Engineering Division**

300 South Madison Avenue  
Greenwood IN 46142

317-881-8698  
greenwood.in.gov